

(718) 476-9202
Fax: (718) 397-7368



Public Service Testing Laboratories, Inc.

A F F I L I A T E D

Non-Destructive Testing Inc.

37-31 57th STREET, WOODSIDE, N.Y. 11377

Report of Analysis

NYS DOH ELAP No.: 10921

Project No.: 14830

Lab. No. A32663

10/01/2001

In the sample of 4 Bulk Materials Collected on 09/29/2001

Your Order No. Telecon

Marked 50 Warren Street, New York, NY, Penthouse South and as below

Submitted for Asbestos Analyses per USEPA Interim Method 600/M4-82-020 {PLM}

We find as follows:

	01	02	03	04
Location:	Window Sill	Roof Drain	1st Floor Lobby	5th Floor Composite

Appearance:	Fibrous	Fibrous	Fibrous	Fibrous
-------------	---------	---------	---------	---------

Color:	Gray	Gray	Gray	Gray
--------	------	------	------	------

% Non-Fibrous:	30.0	25.0	50.0	20.0
----------------	------	------	------	------

% Cellulose:	30.0	25.0	15.0	50.0
--------------	------	------	------	------

% Fiberglass:	40.0	50.0	35.0	30.0
---------------	------	------	------	------

% Other:

% Asbestos as below:

Chrysotile:

Amosite:

Crocidolite:

Other Asbestos:

%Total Asbestos:	0.0	0.0	0.0	0.0
------------------	-----	-----	-----	-----

TO: 50 Warren Street Condominium
c/o Andrews Building Corp.
666 Broadway, 12th Floor
New York, NY 10012

Yours respectfully,
PUBLIC SERVICE TESTING LABORATORIES, Inc.

S. DiMartino, Asst. Laboratory Director

Report on sample by us applies only to lot sampled.

Report on sample by client applies only to sample.

Information contained herein is not to be used for reproduction except by special permission.

Sample retained for thirty days maximum after date of report unless specifically requested otherwise by client.

ENTERED