

ATC Associates

104 East 25 Street, New York, NY 10010

Phone: (212) 353-8280 Fax: (212) 353-8306



Attn: Mr. Fabio Pedone
Warren & Panzer Engineers, P.C.
228 E. 45th Street
New York NY 10017

Fax: (212) 922-0630 Phone: (212) 922-0077

Project: NYC-DEP W & P File # 1079.01.02
53 Nassau Street

Received: 7/3/02 6:00:00 PM
ATC Group #: 8390
Analysis Date: 7/3/02

**Asbestos Fiber Analysis by Transmission Electron Microscopy (TEM) Performed
by EPA 40 CFR Part 763 Final Rule (AHERA)**

Sample	Volume	Area Analyzed	Non Asb	Asbestos Type(s)	# Structures 0.5µ-5 µ	Analytical Sensitivity (S/cc)	Asbestos Concentration (S/mm ²) (S/cc)	Notes
1 8390 -1	1500.00	0.0562	0	None Detected	0	0.0046	<17.79 <0.0046	
2 8390 -2	1500.00	0.0562	0	None Detected	0	0.0046	<17.79 <0.0046	
3 8390 -3	1500.00	0.0562	0	None Detected	0	0.0046	<17.79 <0.0046	
4 8390 -4	1500.00	0.0562	0	None Detected	0	0.0046	<17.79 <0.0046	
5 8390 -5	1500.00	0.0562	0	CHRYBOTILE	0	0.0046	17.79 0.0046	

ROMAN PEYSAKHOV

Analyzed by:

MICHAEL A. GORYCKI, Ph.D.

Approved by:

Disclaimer: The laboratory is not responsible for data reported in structures/cc, which is dependent on volume collected by non-laboratory personnel. This lab is only responsible for data reported in structures/mm². This report may not be reproduced, except in full, without written approval by ATC Associates Inc. This report may not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. This report relates only to the samples reported above. Quality control data (including 95% confidence limits and laboratory and analyst accuracy and precision) is available upon request.

Accredited for NVLAP PLM/TEM #101187-0, NY State ELAP #10878

226 East 45th Street
New York, NY 10017
(212) 922-0877
Fax (212) 922-0639

WARREN & PANZER ENGINEERS, P. C.

AIR MONITORING LOG SHEET/CHAIN-OF-CUSTODY FORM

PAGE 1 OF 1

P.O.

24 hr⁺/a 12 hr⁺/a 6 hr⁺/a 3 hr⁺/a Immediate⁺/a

CLIENT: NY-C DET

PROJECT: 53 WASSAU ST

LOCATION: Roof

W&P FILE #: 1079-01-02

LABORATORY: A.T.C.

ANALYSIS METHOD: PCM

7400

circle one

TECHNICIAN: Dipo ELEM

CONTACT: MIKE NOLAN

LLW#:

SCA JOB#:

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	SAMPLE TYPE	PUMP #	FLOWRATE START STOP	TIME ON	TIME OFF	TOTAL TIME	VOLUME (Meq's)	CONCENTRATION (lb./cc.)
DE70302-1	BY DECAN (IN 49)	TEM		10 10	1000	1230	150	1500	
DE70302-2	INSIDE DOOR (ON 49)	TEM		10 10	1002	1232	150	1500	
DE70302-3	LEFT GGH (ON 51)	TEM		10 10	1004	1234	150	1500	
DE70302-4	RIGHT (ON 51)	TEM		10 10	1006	1236	150	1500	
DE70302-5	MIDDLE (ON 51)	TEM		10 10	1008	1238	150	1500	
DE70302-6	field Blank	N/A		N/A	0	0	0	0	
DE70302-7	"	N/A		N/A	0	0	0	0	
DE70302-8	Sealed Blank	N/A		N/A	0	0	0	0	

COMMENTS:

#8390

SAMPLE BY: Dipo ELEM	DATE: 7/2/02
SIGNATURE: Dipo	
RELEASED BY: John Boyl	DATE: 7.3.02
SIGNATURE: John Boyl	
RECEIVED BY: Michaeli	DATE: 7/3/02
SIGNATURE: Michaeli	6:00 PM

SAMPLE TYPE CODES

1 - Blank	5 - Final Clearance (inside)
2 - Pre-Abatement	6 - Final Clearance (outside)
3 - During Abatement	7 - Personal
4 - During Glove Bag Removal	8 - Background

SEE REVERSE SIDE FOR ANALYSIS INFORMATION



ATC Associates Inc.

104 East 25 Street
New York, NY 10010

TEL: (212) 353-8280 FAX: (212) 353-8306

FACSIMILE TELECOPY TRANSMISSION

To: Mr. Fabio Podone
Warren & Panzer Engineers, P.C.

From: ROMAN PEYSAKHOV

Fax #: (212) 922-0630

ATC Group #: 8390

Date: Wednesday, July 03, 2002

Client Project: NYC-DEP W & P File # 1079.01.02
53 Nassau Street

Time: 11:29:41 PM

Number of Pages: 3

(including cover page)

Comments: