

10/11/2002 17:07 FAX 212 353 8308

ATC

003/007

Attn: Benjamin Sallemi
 ATC Associates Inc
 104 East 25th Street
 New York NY 10010

Received: 10/9/02 8:00:00 AM
 ATC Group #: 8946
 Analysis Date: 10/10/02

Fax: (212) 353-3599 Phone: (212) 353-8280
 Project: DEP Clean-up ATC Project #: 22906-0002
 125 Cedar Street, New York, NY

**Asbestos Fiber Analysis by Transmission Electron Microscopy via NIOSH
 Method 7402**

Sample	Volume	Non Asbestos Fibers	PCM F/cc	Asbestos Type(s)	Asbestos Fibers	Asbestos % of total	7402 Adjusted (TEM) F/cc	Notes
A-9S-08 8946 -8	3890.00	5	0.001	CHRYSTOLE	1	17	0.0002	Cellulose - 2 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-9S-09 8946 -9	3880.00	7	0.001	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Gypsum - 1 Structure, Glass - 2 Structures
A-9S-10 8946 -10	3870.00	8	0	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Glass - 1 Structure
A-8N-11 8946 -11	3870.00	12	0.001	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Gypsum - 4 Structures, Glass - 1 Structure
A-8N-12 8946 -12	3860.00	9	0.001	None Detected	0	0	<0.0013	Cellulose - 6 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-8N-13 8946 -13	3850.00	9	0.001	None Detected	0	0	<0.0013	Cellulose - 6 Structures, Gypsum - 3 Structures
A-8N-14 8946 -14	3840.00	7	0.001	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Gypsum - 1 Structure, Glass - 2 Structures
A-8N-15 8946 -15	3830.00	11	0.001	None Detected	0	0	<0.0013	Cellulose - 5 Structures, Gypsum - 3 Structures, Glass - 3 Structures
A-8S-16 8946 -16	3850.00	7	0.001	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-8S-17 8946 -17	3840.00	9	0.001	None Detected	0	0	<0.0013	Cellulose - 5 Structures, Gypsum - 3 Structures, Glass - 1 Structure

MARK PEYSAKHOV

Analyzed by: *PKing*

MICHAEL A. CORYCKI, Ph.D.

Approved by:

ATC is not responsible for data reported in fibers/cc, which is dependent on volume collected by non-laboratory personnel. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by ATC Associates Inc.

Analysis performed by ATC Associates Inc. (NY ELAP #10379)

Forty Grid Openings from each of the samples were examined for structures greater than 6µm length and width between 0.25 µm and 3µm, and having a length-to-width ratio greater than 3:1

Page 2 of 6

10/11/2002 17:08 FAX 212 353 8306

ATC

004/007

Attn: Benjamin Sallerni
 ATC Associates Inc.
 104 East 25th Street
 New York NY 10010

Received: 10/9/02 8:00:00 AM
 ATC Group #: 8946
 Analysis Date: 10/10/02

Fax: (212) 353-3599 Phone: (212) 353-8280
 Project: DEP Clean-up ATC Project #: 22906-0002
 125 Cedar Street, New York, NY

**Asbestos Fiber Analysis by Transmission Electron Microscopy via NIOSH
 Method 7402**

Sample	Volume	Non Asbestos Fibers	PCM F/cc	Asbestos Type(s)	Asbestos Fibers	Asbestos % of total	7402 Adjusted (TEM) F/cc	Notes
A-8S-18 8946 -18	3830.00	10	0.002	None Detected	0	0	<0.0013	Cellulose - 6 Structures, Gypsum - 3 Structures, Glass - 2 Structures
A-8S-19 8946 -19	3820.00	5	0.001	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Glass - 1 Structure
A-8S-20 8946 -20	3810.00	4	0.001	None Detected	0	0	<0.0013	Cellulose - 2 Structures, Gypsum - 2 Structures
A-7N-21 8946 -21	3820.00	15	0.002	None Detected	0	0	<0.0013	Cellulose - 10 Structures, Gypsum - 5 Structures
A-7N-22 8946 -22	3810.00	8	0.002	None Detected	0	0	<0.0013	Cellulose - 6 Structures, Glass - 1 Structure
A-7N-23 8946 -23	3800.00	11	0.001	None Detected	0	0	<0.0013	Cellulose - 5 Structures, Gypsum - 3 Structures, Glass - 3 Structures
A-7N-24 8946 -24	3790.00	9	0.001	CHRYSTOLE	1	10	0.0001	Cellulose - 8 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-7N-25 8946 -25	3780.00	4	0.001	None Detected	0	0	<0.0012	Cellulose - 3 Structures, Glass - 1 Structure
A-7S-26 8946 -26	3740.00	10	0.001	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Gypsum - 3 Structures
A-7S-27 8946 -27	3730.00	5	0.001	AMOSITE	2	29	0.0003	Cellulose - 2 Structures, Gypsum - 3 Structures

MARK PEYSAKHOV

Analyzed by: 

MICHAEL A. GORYCKI, Ph.D.

Approved by:

ATC is not responsible for data reported in Ebersite, which is dependent on volume collected by non-laboratory personnel. The above report relates only to the items tested. This report may not be reproduced, exact or in full, without written approval by ATC Associates Inc.

Analysis performed by ATC Associates Inc. (NY FLAP 310475).

Forty Grid Openings from each of the samples were examined for structures greater than 5µm length and width between 0.25µm and 3µm, and having a length-to-width ratio greater than 3:1

Page 3 of 6

10/11/2002 17:08 FAX 212 353 8306

ATC

005/007

Attn: Benjamin Sallem

ATC Associates Inc.

104 East 25th Street

New York

NY 10010

Received: 10/9/02

8:00:00 AM

ATC Group #: 8946

Analysis Date: 10/10/02

Fax: (212) 353-3599

Phone: (212) 353-5280

Project: DEP Clean-up ATC Project #: 22906-0002


125 Cedar Street, New York, NY

Asbestos Fiber Analysis by Transmission Electron Microscopy via NIOSH Method 7402

Sample	Volume	Non Asbestos Fibers	PCM F/cc	Asbestos Type(s)	Asbestos Fibers	Asbestos % of total	7402 Adjusted (TEM) F/cc	Notes
A-7S-28 8946 -28	3720.00	5	0.001	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Gypsum - 1 Structure
A-7S-29 8946 -29	3710.00	9	0.001	None Detected	0	0	<0.0013	Cellulose - 3 Structures, Gypsum - 5 Structures, Glass - 1 Structure
A-7S-30 8946 -30	3700.00	6	0.001	None Detected	0	0	<0.0013	Cellulose - 5 Structures, Gypsum - 1 Structure
A-6N-31 8946 -31	3790.00	5	0.002	None Detected	0	0	<0.0013	Cellulose - 4 Structures, Gypsum - 1 Structure
A-6N-32 8946 -32	3780.00	16	0.001	None Detected	0	0	<0.0013	Cellulose - 11 Structures, Gypsum - 4 Structures, Glass - 1 Structure
A-6N-33 8946 -33	3770.00	13	0.001	None Detected	0	0	<0.0013	Cellulose - 11 Structures, Gypsum - 2 Structures
A-6N-34 8946 -34	3870.00	9	0	CHRYSTOLE	1	10	0.00001	Cellulose - 8 Structures, Gypsum - 1 Structure
A-6N-35 8946 -35	3760.00	10	0.002	None Detected	0	0	<0.0013	Cellulose - 9 Structures, Glass - 1 Structure
A-6S-36 8946 -36	3850.00	10	0.001	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-6S-37 8946 -37	3840.00	4	0.002	None Detected	0	0	<0.0013	Cellulose - 3 Structures, Glass - 1 Structure

MARK PEYSAKHOV

Analyzed by:



MICHAEL A. GORYCKI, Ph.D.

Approved by:

ATC is not responsible for data reported in fibers/cc, which is dependent on volume collected by non-laboratory personnel. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by ATC Associates Inc.

Analysis performed by ATC Associates Inc. (NY ELP #10579).

Forty Grid Openings from each of the samples were examined for structures greater than 5µm length and widths between 0.23µ and 3µ, and having a length-to-width ratio greater than 3:1.

Page 4 of 6

10/11/2002 17:09 FAX 212 353 8306

ATC

006/007

Attn: Benjamin Sallemi
 ATC Associates Inc.
 104 East 25th Street
 New York NY 10010


Received: 10/9/02 8:00:00 AM
 ATC Group #: 8945
 Analysis Date: 10/10/02

Fax: (212) 353-3599 Phone: (212) 353-8280
 Project: DEP Clean-up ATC Project #: 22906-0002
 125 Cedar Street, New York, NY

**Asbestos Fiber Analysis by Transmission Electron Microscopy via NIOSH
 Method 7402**

Sample	Volume	Non Asbestos Fibers	PCM F/cc	Asbestos Type(s)	Asbestos Fibers	Asbestos % of total	7402 Adjusted (TEM) F/cc	Notes
A-6S-38 8946 -38	3830.00	10	0.001	CHRYBOTILE	1	9	0.0001	Cellulose - 7 Structures, Gypsum - 3 Structures
A-6S-39 8946 -39	3820.00	6	0.001	None Detected	0	0	<0.0013	Cellulose - 1 Structure, Gypsum - 3 Structures, Glass - 2 Structures
A-6S-40 8946 -40	3810.00	10	0.002	CHRYBOTILE	2	17	0.0003	Cellulose - 3 Structures, Gypsum - 2 Structures, Glass - 5 Structures
A-41 8946 -41	3800.00	12	0.001	CHRYBOTILE	1	8	0.0001	Cellulose - 4 Structures, Gypsum - 3 Structures, Glass - 5 Structures
A-42 8946 -42	3790.00	7	0.002	None Detected	0	0	<0.0013	Cellulose - 3 Structures, Gypsum - 2 Structures, Glass - 2 Structures
A-43 8946 -43	3800.00	11	0.001	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Gypsum - 1 Structure, Glass - 3 Structures
A-44 8946 -44	3800.00	15	0.002	CHRYBOTILE	1	6	0.0001	Cellulose - 12 Structures, Gypsum - 2 Structures, Glass - 1 Structure
A-45 8946 -45	3800.00	16	0.002	None Detected	0	0	<0.0013	Cellulose - 7 Structures, Gypsum - 8 Structures, Glass - 1 Structure
A-46 8946 -46	3790.00	18	0.001	None Detected	0	0	<0.0013	Cellulose - 9 Structures, Gypsum - 8 Structures, Glass - 1 Structure
A-47 8946 -47	3800.00	11	0.001	None Detected	0	0	<0.0013	Cellulose - 10 Structures, Gypsum - 2 Structures, Glass - 1 Structure

MARK PEYSAKHOV

Analyzed by: 

MICHAEL A. GORYCKI, Ph.D.

Approved by:

ATC is not responsible for data reported in fibers/cc, which is dependant on volume collected by non-laboratory personnel. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by ATC Associates Inc.

Analysis performed by ATC Associates Inc. (NY ECLAP #10679).

Forty Grid Openings from each of the samples were examined for structures greater than 5µm length and width between 0.25µm and 1µm, and having a length-to-width ratio greater than 3:1.

Page 5 of 6

10/11/2002 17:09 FAX 212 353 8308

ATC

007/007

Attn: Benjamin Salieri
 ATC Associates Inc.
 104 East 25th Street
 New York NY 10010

Received: 10/9/02 3:00:00 AM
 ATC Group #: 8946
 Analysis Date: 10/10/02

Fax: (212) 353-3599 Phone: (212) 353-8280

Project: DEP Clean-up ATC Project #: 22906-0002
 125 Cedar Street, New York, NY

**Asbestos Fiber Analysis by Transmission Electron Microscopy via NIOSH
 Method 7402**

Sample	Volume	Non Asbestos Fibers	PCM F/cc	Asbestos Type(s)	Asbestos Fibers	Asbestos % of total	7402 Adjusted (TEM) F/cc	Notes
A-48 8946 -48	3800.00	13	0.001	None Detected	0	0	<0.0013	Cellulose - 9 Structures, Gypsum - 3 Structures, Glass - 1 Structure

MARK PEYSAKHOV

Analyzed by: 

MICHAEL A. GORYCKI, Ph.D.

Approved by:

ATC is not responsible for data reported in fiber/cc, which is dependent on volume collected by non-laboratory personnel. The above report relates only to the items tested. This report may not be reproduced, except in full, without written approval by ATC Associates Inc.

Analysis performed by ATC Associates Inc. (NY ELAP #10679).

Forty Grid Openings from each of the samples were examined for structures greater than 5µm length and width between 0.25µ and 5µ, and having a length-to-width ratio greater than 3:1

Page 6 of 6