

ATC Associates

111 West 25 Street, New York, NY 10010

Phone: (212) 353-8280 Fax: (212) 353-8306

Client: Mr. Fabio Pedone

Warren & Panzer Engineers, P.C.

228 E. 45th Street

New York

NY 10017

Fax: (212) 922-0630

Phone: (212) 922-0077

Project: NYC DEP, W&P# 1079.01.02

14 Vesey Street

Received: 7/20/02

1:00:00 PM

ATC Group #: 8554

Analysis Date: 7/21/02

Asbestos Fiber Analysis by Transmission Electron Microscopy (TEM) Performed by EPA 40 CFR Part 763 Final Rule (AHERA)

Sample	Volume	Area Analyzed	Non Asb	Asbestos Type(s)	# Structures 0.5µ-5 µm	Analytical Sensitivity (S/cc)	Asbestos Concentration (S/mm ³)	(S/cc)	Notes
001A 8554 -1	1560.00	0.0562	0	None Detected	0	0	0.0044	<17.79	<0.0044
002A 8554 -2	1560.00	0.0562	0	None Detected	0	0	0.0044	<17.79	<0.0044
003A 8554 -3	1560.00	0.0562	0	None Detected	0	0	0.0044	<17.79	<0.0044
004A 8554 -4	1560.00	0.0562	0	None Detected	0	0	0.0044	<17.79	<0.0044
005A 8554 -5	1560.00	0.0562	0	None Detected	0	0	0.0044	<17.79	<0.0044

ROMAN PEYSAKHOV

Analyzed by:

MICHAEL A. GORYCKI, Ph.D.

Approved by:

Disclaimer: The laboratory is not responsible for data reported in structures/cc, which is dependent on volume collected by non-laboratory personnel. This lab is only responsible for data reported in structures/mm³. This report may not be reproduced, except in full, without written approval by ATC Associates Inc. This report may not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. This report relates only to the samples reported above. Quality control data (including 95% confidence limits and laboratory and analysis accuracy and precision) is available upon request.

Accredited for NVLAP PLM/TEM #101167-0, NY State ELAP #10879

Page 1 of 1

23

224 East 45th Street
New York, NY 10017
(212) 922-6877
Fax (212) 922-0630

WARREN & PANZER ENGINEERS, P. C.

AIR MONITORING LOG SHEET/CHAIN-OF-CUSTODY FORM

24 hr⁺/a 12 hr⁺/a 6 hr⁺/a 3 hr⁺/a Immediate ⁺/a

W&P FILE #: 105A 01-02

LABORATORY: ATC

ANALYSIS METHOD: PGM TEM AHEBA EPA LEVEL II

TECHNICIAN: N. Wells

P.O.

CONTACT: Mike Nolan

CLIENT: NYC-DEP

PROJECT: Roof Clearance

LOCATION: 14 West St

SAMPLE NUMBER	SAMPLE DESCRIPTION/LOCATION	SAMPLE TYPE	PUMP #	FLOWRATE START STOP	ON	OFF	TOTAL TIME	VOLUME (liters)	CONCENTR (lb./cc.)
001A	Enter to roof	3		4	08:00	14:30	390	1560	
002A	Cur area - roof	3		4	08:01	14:31	390	1560	
003A	Right side roof	3		4	08:02	14:32	390	1560	
004A	Left side roof	3		4	08:03	14:33	390	1560	
005A	Right side roof	3		4	08:04	14:34	390	1560	
006	Field	1							
007	Field	1							
008	Sealed	1							

COMMENTS: Breakdown - then go to lab
of last sample is sent to lab!

SAMPLE BY: N. Wells
SIGNATURE: [Signature]
RELEASED BY: [Signature]
SIGNATURE: [Signature]
RECEIVED BY: ATC Petra Lab
SIGNATURE: [Signature]
DATE: 3/19
DATE: 07.20.02
DATE: 1300

SAMPLE TYPE CODES	
1 - Blank	5 - Final Clearance (inside)
2 - Pre-Abatement	6 - Final Clearance (outside)
3 - During Abatement	7 - Personal
4 - During Glove Bag Removal	8 - Background

THIS REVERSE SIDE FOR ANALYSIS INFORMATION



ATC Associates Inc.

104 East 25 Street

New York, NY 10010

TEL: (212) 353-8280 FAX: (212) 353-8306

FACSIMILE TELECOPY TRANSMISSION

To: Mr. Fabio Pedone
Warren & Panzer Engineers, P.C.

From: ROMAN PEYSAKHOV

Fax #: (212) 922-0630

ATC Group #: 8554

Date: Monday, July 22, 2002

Client Project: NYC DEP. W&P# 1079.01.02
14 Vesey Street

Time: 9:53:33 AM

Comments:

Number of Pages: 2
(including cover page)

22