

Draft2 Comments by Covino Environmental Associates, Inc.
January 6, 2003

~~16.17.~~ Disengage the local capture system and relocate to another section of the duct to be cleaned.

X 18. Prior to dismantling work area preparations, clean interior walls of temporary containments using wet-wiping or HEPA vacuum methods.

19. Occupied areas or common areas in which fan unit cleaning is accomplished, will be cleaned as common spaces using the common space unit prices, immediately after the HVAC cleaning is complete.

X 20. These areas identified in 19 above will be air tested immediately after cleaning of the common space and analysis will be accomplished on a RUSH basis. These areas should not be opened for re occupancy until successful results are received.

~~17.21.~~ All work will be accomplished by DEP certified Asbestos Handlers.

~~18.22.~~ All work will be supervised by a DEP certified Asbestos Handler Supervisor.

~~19.23.~~ All work will be overseen by a NADCA certified ASCS or equivalent.

~~20.24.~~ Workers will utilize $\frac{1}{2}$ face APR's, eye protection and full body coveralls during the cleaning process.