

02/18/99 17:15 FAX 2122190256

SWANKE HAYDEN CONNELL

003

02/18/99 13:00 FAX 212 738 3318

COSENTINI ASSOCIATES

003/003

COSENTINI ASSOCIATES LLP • TWO PENN. PLAZA, NEW YORK, NY 10121 • 212-615-3600 • FAX 212-615-3700

Page - 2 -

After all construction work (set-up adjustment, control and monitoring system, etc.) will be completed and information regarding additional LAN/Communication equipment will be available, we will evaluate the conditions and, if necessary, will issue recommendations for upgrade/improvement.

X:\W7\FILES\145499\NCVL0212.M01

02/16/99 17:15 FAX 2122190256

SWANKE HAYDEN CONNELL

004

02/16/99 13:25 FAX 212 738 3519

COSENTINI ASSOCIATES

002

Cosentini Associates LLP
Consulting Engineers

**UPS FOR AUDIO VISUAL
OEM
FEBRUARY 16, 1999**

Add 50 KVA UPS system with 20 minute battery supply. An 8' x 9' room with conditioned air will be required to house this equipment. A feeder from the UPS to the panel presently provided for the AV equipment will be required. Wire UPS to all AV equipment. Provide a 2 ton water cooled DX unit supplied by emergency power. Exact location of UPS and A/C unit has not yet been determined.

X:\WP\FILES\MMTM0216.G01