



ROBERT B. SAMUELS INC.

Electrical Contractors

October 14, 1998

Ambassador Construction Company
 317 Madison Avenue
 New York, NY 10017

Attn: Mr. Martin Schneider

Re: OEM - RBS Job #54605

Dear Sir:

The following is our quotation for changes on the plans dated 9/3/98 and 9/25/98, representing change items #3 & 4.

1. Relocate panel ELP 23N3 in the LAN room. The panel had been previously installed, along with branch conduits. All conduits had to be relocated. Reference Drawing #E1-23 dated 9/25/98. Cost.....\$3,300.00
2. Tap the secondary of the 75 KVA transformer and feed a new 200 Amp switch with shunt trip. This is done to re-direct the feed to ATS #7 on the roof. Reference Drawing #E3-01 dated 9/3/98. Cost.....\$4,310.00
3. Provide service connection to 208 volt single phase dishwasher per Drawing E1-23 dated 9/25/98. Cost..\$1,740.00
4. Add (1) fire alarm pull station. Cost..\$ 950.00
5. Upgrade wiring to dimming panel from new breaker in panel EDPL-23E. It will now be fed by a 70 Amp breaker.
 Cost..\$1,825.00
6. Additional switching, room 2330. Includes new and relocated wiring. Cost.....\$ 640.00
7. Per drawing E4-02 dated 9/25/98 -
 - 1 - Add (1) 200 Amp, 3 pole and (1) one 3 pole 70A breaker in EDPL-23E.
 - 2 - Delete (1) 3 pole 100 Amp breaker in EDPL-23E.

- 1 -

NOV 17 '98 16:03 FR AMBASSADOR CONSTR. CO212 949 9762 TO 6694107

P.06/36

OCT 14 1998 14:55 FR R.B.SAMUELS

212 213 4089 TO AMBASSADOR

P.03/03



ROBERT B. SAMUELS INC.

Electrical Contractors

October 14, 1998

Mr. Martin Schneider

VOID -

- 3 - Revise panel ULP-23W and ULP-R from 3 phase, 4 wire to 1 phase, three wire.
- 4 - Add (1) 50A 2 pole breaker in panel ELP-23C1.
- 5 - Delete (2) 15 Amp 1 pole breakers in panel ELP-23C1.

All of these panels have been delivered and installed, including branch circuitry and feeders.

Panel EDPL23-E will have to be replaced in its entirety. All branch and feeder wiring will be removed and then re-installed.

Panel ULP23W and R will also have to be replaced. New panels will be provided and re-installed.

New breakers will be furnished for panel ELP-23C-1.
Cost.....\$17,400.00

If you have any questions, please do not hesitate to call.

Very truly yours,

ROBERT B. SAMUELS INC.

Gary A. Fishbone
Project Manager

GAF:rr