

OCT 08 '98 13:30 FR AMBASSADOR CONSTR. CO212 949 9762 TO 6694107

P.02/03

AMBASSADOR CONSTRUCTION CO., INC.



October 8, 1998

Mr. Walter Weems
Silverstein Properties, Inc.
7 World Trade Center
New York, NY 10048

RE: Mayor's Office of Emergency Management
7 World Trade Center - 1, 7 & 23rd Floors
Change Order #015
Amb. Job # S57-5175

Dear Mr. Weems:

We are pleased to submit herewith our change order #015 to perform the following work at the above referenced premises for the sum of TWENTY ONE THOUSAND TWO HUNDRED THIRTY FOUR DOLLARS (\$21,234.00):

SCOPE OF WORK

As per Swanke Hayden Connell's sketch for new sleeve location at 23rd Floor (attached), the following is our breakdown:

- (41) 4" through-wall sleeves @ \$283.38	\$11,619.00
- (4) 2" underfloor sleeves @ \$141.00	564.00
- 4" stubs from ceiling to below raised floor at 15' of conduit with elbows 15 x 4=60' x \$42.29	2,537.00
- Carpenter's time for cutting, patching and firestopping of wall	3,100.00
- Cutting of raised floor panel	500.00
Subtotal	\$18,320.00
General Conditions	1,465.00
Overhead & Fee	1,187.00
Insurance	262.00
Total	\$21,234.00

Please notify us if we are to proceed with this work.

We trust the above meets with your approval and we look forward to the continued pleasure of serving you.

Very truly yours,

AMBASSADOR CONSTRUCTION CO., INC.


Martin Schneider
Vice President

cc: Juan Mejia - SHC
Glenn Pymonto - DCAS

Accepted: _____ Dated: _____
c:\wpdocs\oem[oemco15.wpd]

317 MADISON AVENUE, NEW YORK, NY 10017, 212 922 1020. FAX 212 949 9762

NEW SHEUTE LOCATIONS @ 23RD FL

2- GIC TO FIRE STP? ALL
SLEEVES @ CORE WALL
AFTER INSTALLATION OF
CABLES

NOTES

1- SLEEVES @ EOC SHOULD BE
LOCATED ABOVE CORE ELS.
BT INSIDE EOC IS NOT
CRITICAL

4" φ SLEEVE LENGTH AS PER
FOR EASY ACCESS. U.O.N

