



Adjustable

Date: 05/22/1998

Page 1

AMBASSADOR CONSTRUCTION
317 Madison Avenue
NEW YORK, NY 10017

RE: Mayor's Office
Our Ref.#: 7139

Attn: Jack Klein

Dear Jack,

We are pleased to submit our proposal to furnish, deliver and install the following units:

STORAGE ROOM 23-24

1. "Type N&B" Nut and Bolt Heavy Duty Shelving Units. Please note that once shelves are installed they are non-adjustable.
Each unit shall have 9 shelves, which includes the top and bottom shelf, providing 8 openings.

3 Starter Units	18"D	X	48"W	X	99"H
1 Starter Units	24"D	X	36"W	X	99"H
1 Starter Units	24"D	X	30"W	X	99"H

5 Total Units

Paint finish: - 00 Standard Finish - Advise

>>Above units to be of open sides and open backs with sway bracing as required.

STORAGE ROOM 23-24 Summary /

5 Shelving Units

Material

\$1,059.00 NET

OK



Adjustable

Date: 05/22/1998

Page 2

AMBASSADOR CONSTRUCTION
317 Madison Avenue
NEW YORK, NY 10017

RE: Mayor's Office
Our Ref.#: 7139

Attn: Jack Klein

CLOSET 23-16

1. "Type LR" All Metal Library Reinforced Bookcase Units with adjustable shelves.
Each unit shall have 7 shelves, plus a top and bottom shelf, providing 8 openings.

1 Starter Units	15"D	X 42"W	X 101.375"
2 Adder Units	15"D	X 42"W	X 101.375"
3 Backs	42"W	X 101.375"H	

3 Total Units

Paint finish: - 00 Standard Finish - Advise

CLOSET 23-16 Summary

3 Shelving Units

Material

\$1,315.00 NET

ROOM #35/ 38

1. "Type LR" All Metal Library Reinforced Bookcase Units with adjustable shelves.
Each unit shall have 7 shelves, plus a top and bottom shelf, providing 8 openings.



Adjustable

Date: 05/22/1998

Page 3

AMBASSADOR CONSTRUCTION
317 Madison Avenue
NEW YORK, NY 10017

RE: Mayor's Office
Our Ref.#: 7139

Attn: Jack Klein

2 Starter Units	15"D	X 36"W	X 101.375"
8 Adder Units	15"D	X 36"W	X 101.375"
10 Backs	36"W	X 101.375"H	
2 Starter Units	15"D	X 42"W	X 101.375"
3 Adder Units	15"D	X 42"W	X 101.375"
5 Backs	42"W	X 101.375"H	

15 Total Units

Paint finish: - 00 Standard Finish - Advise

ROOM #35 Summary

15 Shelving Units

Material

\$6,043.00 NET

WATER STORAGE 23-25

1. "Type N&B" Nut and Bolt Heavy Duty Shelving Units. Please note that once shelves are installed they are non-adjustable.
Each unit shall have 7 shelves, which includes the top and bottom shelf, providing 6 openings.

1 Starter Units	30"D	X 36"W	X 75"H
3 Starter Units	30"D	X 42"W	X 75"H

4 Total Units



Adjustable

Date: 05/22/1998

AMBASSADOR CONSTRUCTION
317 Madison Avenue
NEW YORK, NY 10017

Page 4

RE: Mayor's Office
Our Ref.#: 7139

Attn: Jack Klein

Paint finish: - 00 Standard Finish - Advise

>>All of the above units to be of open sides and open backs
with sway bracing as required.

>>PAINT FINISH FOR ALL PRODUCT IS BASED ON OUR STANDARD
SELECTION. PLEASE BE ADVISED THAT THERE IS A 5% OR
\$300.00 NET MINIMUM UPCHARGE PER CUSTOM PAINT MATCH.

IMPORTANT NOTE: A 50% DEPOSIT IS DUE WITH PURCHASE ORDER
BALANCE PRIOR TO DELIVERY.

WATER STORAGE 23-25 Summary

4 Shelving Units

Material

\$879.00 NET

Proposal Summary

27 Shelving Units

Material

Delivery - Union R/T

Installation - Union R/T

\$9,296.00 NET
\$405.00 NET
\$2,025.00 NET

11,726

PLEASE NOTE QUOTE NUMBER ON PURCHASE ORDER.