

MAY-19-1998 16:02

SIRINA FIRE

5169420415 P.02/03


SIRINA

FIRE PROTECTION CORP.

May 19, 1998

Ambassador Construction, Co. Inc.
317 Madison Avenue
New York, NY 10017

Attn: Jack Klein

Re: Mayor's Office
1 World Trade Center
1st, 7th & 23rd Floors
REVISED

Gentlemen:

We are prepared to furnish the necessary labor and material to install automatic sprinklers at the above referenced project in accordance with drawings FP1.01, Fp2.07, FP3.23, FP4.23, FP5.23 & FP6.23, dated May 4, 1998. *not latest.*

Our scope breakdown is as follows:

1st Floor Install 3 concealer heads.
Rebate Install 1 fire hose cabinets with 30' of 4" bulk piping.
Connect to existing system.
Demo existing branch line..

7th Floor Install 5 concealer heads.
Install 6 upright heads.
Install 150' of 2 1/2" sprinkler main.
Disconnect and cap existing; demo by others.

23rd Floor Install 284 concealer heads.
Install 27 upright heads
Install 2 preaction valve assemblies.
Furnish all electric equipment for installation by others.
Install 15 concealer heads (preaction system)
Install 15 upright heads (preaction system)
Install 100 of 2 1/2" sprinkler main.
Make connections to existing main.
Disconnect and cap existing; demo by others.
Install 2 fire hose cabinets with 100' of 4" bulk piping.
Connect to existing fire standpipe riser on overtime.

284
27
301
15
316
15
331
112

284
27
301
15
316
15
331
112

284
27
301
15
316
15
331
112

MAY-19-1998 16:02

SIRINA FIRE

5169420415 P.03/03

**SIRINA****FIRE PROTECTION CORP.**

Ambassador Construction Co., Inc.

Mr. Jack Klein

May 19, 1998

Page 2 of 2

All heads center line of tile +/- 1/2".

All work done during normal working hours.

For this installation, we are pleased to quote the sum of One Hundred Thirty Nine Thousand Three Hundred Twenty Five (\$139,325.00) Dollars.

We exclude NYC filing, electric wiring, asbestos conditions, phasing, temporary fire protection, fire extinguishers and cabinets, Class "E" connections and/or modifications, painting, patching and firewatch.

Thank you for the opportunity of working with you. If you have any questions, please contact us.

Very truly yours,

SIRINA FIRE PROTECTION CORP.

Matthew Allgeier

MA:mm
mayors office

Sheet1

Fire Protection				
foam system for tanks			10000	??
bells, lights, manual pull stations & horns, connection to fire alarm panel by electrical contractor				
sprinkler /23rd flr	41760	2.4/SF	100224	99190
Preaction			20000	16400
sprinkler /7th floor	3626	2.4/sf	9000	10810
Fire Hose Cabinets	3	1600	4800	5100
total			144024	131500