

MAY-20-1998 10:24

PREMIER WOODCRAFT, LTD

16103834172 P.02/03

PREMIER WOODCRAFT LTD.

131 Birch Street, S. Coatesville PA 19320-4014
 PHONE (610)383-6624 FAX (610)383-4172

ESTIMATE

JOB NAME	Mayor's OEM	ARCHITECT	Swanke Heydon Connell
ADDRESS	7 World Trade	LATEST DATE ON DWG.	04/06/98
		ESTIMATE DATE	05/20/98 10:01:18 AM
FLOOR	Twenty third	ESTIMATOR	ERIC SVALGARD

WORK INCLUDED :

<u>Item #</u>)Description	<u>Qty</u>	<u>unit</u>
1)Double sided file enclosure at room 23-39 and 41	54	LF
2)Wall cabinets at East wall of 23-41	12	LF
open file enclosure below	12	LF
2a)Wall cabinets at west wall of 23-39	6	LF
3)Shelf and pole at coat closets	29	LF
adjustable shelves at storage closets	40	LF
4)Anoline dyed makore reception desk with solid mahogany accent strips	17	LF
credenza at back wall with file and box drawers and p. lam counter	5	LF
Corian transaction counter on 1/4" aluminum pin supports	14	LF
Monitor drop	1	Ea.
5)Flush paint grade wood base at reception and elevator lobby	216	LF
6)Marlite faux wood panels at recep., mayors office and EOC	3108	Sq. ft.
7)P. lam wall and base cabinets at pantry 23-21	13	LF
wall cabinet only over refrigerator	3	LF
8)P. lam adjustable shelves at 23-20	12	LF
open file enclosure below	6	LF
9)Makore A/V wall unit in Commissioner's office 23-15	11	LF
makore base moulding	90	LF
makore bookcase cabinets with doors below counter top	6	LF
10)pen file enclosure with counter top at 23-13 Comm. suite (!)	12	LF
✓ 11)Closet interior and louvered doors at bathroom 23-12	1	Pr.
P. lam base cabinets with corian counter top	4	LF
✓ 11a)Closet interior and louvered door at bathroom 23-08	1	Ea.
P. lam base cabinets with corian counter top	4	LF
12)Makore bookcase cabinets with doors below counter top room 23-09	9	LF
7a)P. lam wall and base cabinets at pantry 23-06	10	LF
9)Makore A/V wall unit in Mayor's conference room	16	LF
13)P. lam base cabinets with counter and adjustable shelves at 23-49	19	LF
14)P. lam base cabinets with counter at 23-45/46	13	LF
15)P. lam adjustable shelves at room 23-25	60	LF
16)P. lam base cabinets at room 23-44,45,46	13	LF

MAY-20-1998 10:24

PREMIER WOODCRAFT, LTD

16103834172 P.03/03

Mayor OEM.DOC PREMIER Page 2

17) Wood doors

Type A-Flush door 2 1/4" thick with makore wood veneer	10	Ea.
Type I-Custom louver door with header	1	Ea.
Type H-Pair of louver doors with header	1	Pr.
Type C-Pair of flush makore doors	8	Pr.

Header for type C pairs	2	Ea.
Wood door frames makore finish	16	Ea.

TOTAL \$ 346,500.00

PRICE EXCLUDES ALL OVERTIME, TEMPORARY PROTECTION AND HOISTING CHARGES. ALL FURNISH ONLY (F/O) DOOR PRICES INCLUDE PREFINISHING PREMACHINING AND TAILGATE DELIVERY TO JOBSITE. ALL DOOR PRICES EXCLUDE FURNISHING OF HARDWARE. DOOR INSTALLATION INCLUDES INSTALLATION OF ASSOCIATED HARDWARE.

Page 2 of 2