



Founded 1931

Fabricators & Erectors of Structural and Ornamental Iron

May 19, 1998

126-85 WILLETS POINT BOULEVARD
FLUSHING, NEW YORK 11368
Telephone: 718-899-8300
Fax: 718-335-3243

Ambassador Construction Corp. Inc.

Att: Mr. Jack Klein;

Re: MAYORS OFFICE OF EMERGENCY MANAGEMENTSCOPE OF WORK INCLUDED IN BID

- 1) F & I structural steel framing. —
- 2) F & I metal floor decking. (as specified) —
- 3) F & I steel frame with posts & McNichols grating @ fuel oil pump room —
(page A1-1 & Sect 9)
- 4) F & I one (1) new bilco door & rung type ladder — Page A1-1 —
- ALTERNATE 5) F & I new wire mesh Wall @ 7'-0" high with two (2) swinging gates with locks. — 7,500⁻
(P A 23-1)
- 6) F & I 2 x 2 @ 6" long angle clips @ top of masonry partition wall. Approximately
75 linear feet (or 75 clips) @ partition type 10 only (P A1-1)
- OUT 7) F & I steel tubes @ A/V enclosures Page D-3. (two (2) sections only. Tubes to be
bolted to floor and ceiling. Tubes @ 2 x 2 to be strapped together. Tubes @ 4 x 4
to be erected loose. Layout of location by others. — 9,000⁻
- 8) F & I 1/4 plate walls, Ceilings & Floor, @ room 12 x 10 x 9'-0" high @ page D-10.
Plates to be seam welded together (no grinding of welds). Channel framing at
walls & ceilings to be bolted together. Access with freight elevator assumed to
deliver & unload materials.
- 9) Furnish only to be installed by others one (1) galvanized tube frame (4 x 4 tube) 2,800⁻
@ door @ section 3/D12.
- ALTERNATE 10) F & I five (5) Antenna support frames on page S5. — 33,000⁻
- 11) F & I steel @ roof of Radio Room — Page S4. —

Any and all other work other than specifically included in this estimate is excluded
from this proposal.

page 2 of 2

295,000⁻