NYC 9/11 Public Portal Document

DEPARTMENT OF CITYWIDE ADMINISTRATIVE SERVICES
OFFICE OF THE GENERAL COUNSEL

MUNICIPAL BUILDING, 16th Floor
NEW YORK, N.Y. 10007
(212) 669-8400 Fax: (212) 669-8558
E-Mail: dcaslegal@dcas.nyc.gov

WILLIAM J. DIAMOND
Commissioner

PHILIP DAMASHEK
General Counsel/
Deputy Commissioner For Legal Services

DCAS/GENERAL COUNSEL
2001 APR 16 P 4:09

Joint Asbestos Survey Report

Agency: Dept of Juvenile Justice

Address: 365 Broadway N y, N y

Project #: Not given Floors: 2, 3, 4 and 5

Reviewed by: Karlene Daniels Date: 4/16/01

Renovation: Yes_____ No_____ AHERA: Yes_____ No ✓

Asbestos Found: Yes ✓ No_____ O&M Recommended: Yes ✓ No_____

Material Type/ Location	Approximate Amount/ Condition	Sample #/ % Asbestos	Recommended Action
Miscellaneous Material Floor tiles- 12" x 12" floor tiles, various colors throughout 2nd, 3rd, 4th and 5th floors.	Not estimated/ good condition	1.5-20% asbestos	Material is in good condition at the present time. Implement an Operations and Maintenance program designed to prevent damage or disturbance to asbestos containing materials (ACM). Continue O&M program until all ACM is removed. Based on a report issued by Ambient Group Inc. on 3/28/01.

The Official New York City Web Site
nyc.gov

EXR

NYC-WTC_000182348

NYC 9/11 Public Portal Document

Joint Asbestos Survey Report

Agency: _____

Address: _____

Material Type/ Location	Approximate Amount/ Condition	Sample #/ % Asbestos	Recommended Action
Miscellaneous Material Ceiling Tiles-1' x 1' and 3' x 2', 3rd and 5th floors. Ceiling Plaster- 3rd-5th floors Wall Plaster- 2nd-5th floors	Not estimated	0% ACM 0% ACM 0% ACM	No exposed asbestos containing materials (ACM) was found in the area (s) specified above at the time of the survey. If any renovation/demolition work is performed and ACM is uncovered, then work is to be done in accordance with OSHA, EPA, STATE and LOCAL governmental regulations pertinent to asbestos abatement procedures.

NYC-WTC_000182349