

ATC Associates

104 East 25 Street, New York, NY 10010

Phone: (212) 353-8280 Fax: (212) 353-8306



Attn: John Anuforo

Cole Consulting Corp.

2269 Saw Mill River Road

Elmsford

NY 10523

Fax: (914) 345-0045

Phone: (914) 345-6000

Project: FDNY Training Academy

Engine Company 23. Inside Fire Truck

Received: 6/8/02

6:00:00 PM

ATC Group #: 8017

Analysis Date: 6/9/02

**Asbestos Fiber Analysis by Transmission Electron Microscopy (TEM) Performed
by EPA 40 CFR Part 763 Final Rule (AHERA)**

Sample	Volume	Area		Non Asb	Asbestos Type(s)	# Structures		Analytical	Asbestos	Notes
		Analysed	Concentration			0.5µ-5µ	5µ	Sensitivity (S/cc)	Concentration (S/mm ²) (S/cc)	
AQT-1 8017 -1	450.00	0.1124	0	0	None Detected	0	0	0.0076	<8.90 <0.0076	Fiber Glass - None Detected Silicon - None Detected

Truck # SP-9707

ROMAN PEYSAKHOV

Analyzed by:

MICHAEL A. GORYCKI, Ph.D.

Approved by:

Disclaimer: The laboratory is not responsible for data reported in structures/cc, which is dependent on volume collected by non-laboratory personnel. This lab is only responsible for data reported in structures/mm². This report may not be reproduced, except in full, without written approval by ATC Associates Inc. This report may not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. This report relates only to the samples reported above. Quality control data (including 95% confidence limits and laboratory and analysis accuracy and precision) is available upon request.

Accredited for NVLAP PLM/TEM #101187-0, NY State ELAP #10879

Page 1 of 1

CITY_21MC100_010222157

8017

ENVIRONMENTAL TECHNOLOGIES

2269 Saw Mill River Road - Bldg. 5
Elmsford, NY 10523
914-345-6000

ASBESTOS AIR SAMPLE COLLECTION
& CHAIN OF CUSTODY

SITE FDNY TRAINING ACADEMY

DATE 5-7-02

PROJECT # ENGINE COMPANY 23

PANDAZZ ISLAND

TECHNICIAN ABAYOMI O. SHOJO

SIGNATURE ALV

CONTACT/PHONE 914-345-6000

ROTOMETER#

Battalion#

Daily Activity: Inside Fire truck

CASSETTE TYPE: 25mm 37mm POLYCARBONATE

ANALYSIS REQUESTED: PCM TEM A Q T

Test Performed: Pre: Dur: Post P=Pass F=Fail

SAMPLE#	LOCATION	TIME START	TIME STOP	TOTAL MIN	FLOW RATE INIT/FINAL	VOL. LITERS	FIBERS PER CC	P/F
AQT-1	Inside truck#	3:10	4:40	90	5 15	450		
	SP-9707				//			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			
					/			

ANALYZED BY: _____ DATE ANALYZED: _____

COMMENTS: _____

SENT TO	DATE	TIME	# OF SAMPLES	RECEIVED BY	DATE	TIME
ATC	5/7		(1)	N. Groff	6.8.02	18:00