New York Lab
307 West 38th Street, New York, NY 10018
Phone: 212-290-0051 Fax: 2122900058 Email:

EMSL

Attn: Howard Bader
H.A. Bader Consultants
88 Bleecker St
Suite 4E
New York, NY 10012
Fax: (212) 477-8941 Phone: 212-475-4122
Project: **DC 37 / 125 Barclay Street, NY, NY / Revised Report 9/26/01**

Customer ID: HAB50
Customer PO:
Received: 09/25/01 5:00 PM

EMSL Order: 030104914
EMSL Project ID:

Analysis Date: 9/26/2001

Asbestos Analysis of Bulk Materials by PLM via the NY State ELAP 198.1 Method

Sample	Location	Appearance	Treatment	Non-Asbestos % Fibrous	Non-Asbestos % Non-Fibrous	Asbestos % Type
D101 *030104914-0001*	10th Fl Carpet Rm 1001 N	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 35.00% Cellulose	15.00% Quartz 40.00% Non-fibrous (other)	None Detected
D102 *030104914-0002*	10th Fl Carpet Rm 1000 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 40.00% Cellulose	10.00% Quartz 40.00% Non-fibrous (other)	None Detected
D103 *030104914-0003*	9th Fl Carpet Rm 980 N	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 30.00% Cellulose	10.00% Quartz 50.00% Non-fibrous (other)	None Detected
D104 *030104914-0004*	9th Fl Carpet Rm 901 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 35.00% Cellulose	10.00% Quartz 45.00% Non-fibrous (other)	None Detected
D105 *030104914-0005*	8th Fl Carpet Rm 811 N	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 30.00% Cellulose	10.00% Quartz 50.00% Non-fibrous (other)	None Detected
D106 *030104914-0006*	8th Fl Carpet Rm 814 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 45.00% Cellulose	10.00% Quartz 35.00% Non-fibrous (other)	None Detected
D107 *030104914-0007*	7th Fl Carpet Rm 730 N	Gray Fibrous Heterogeneous	Teased Dissolved	15.00% Glass 40.00% Cellulose	10.00% Quartz 35.00% Non-fibrous (other)	None Detected
D108 *030104914-0008*	7th Fl Carpet Rm 780 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 45.00% Cellulose	5.00% Quartz 40.00% Non-fibrous (other)	None Detected
D109 *030104914-0009*	6th Fl Carpet RM 640 Middle	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 35.00% Cellulose	55.00% Non-fibrous (other)	None Detected
D110 *030104914-0010*	6th Fl Carpet RM 640 Middle	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 25.00% Cellulose	65.00% Non-fibrous (other)	None Detected

Williams John
Analyst

Laboratory Manager
or other approved signatory

PLM has been known to miss asbestos in a small percentage of samples which contain asbestos. Negative PLM results cannot be guaranteed. Samples reported as <1% or none detected should be tested with TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. The above test must not be used by the client to claim product endorsement by NVLAP nor any agency of the United States Government.
Analysis performed by EMSL Manhattan (NVLAP #101048-0), NY ELAP 11506

PLM PointCount-1

NYC 9/11 Public Portal Document

New York Lab
307 West 38th Street, New York, NY 10018
Phone: 212-290-0051 Fax: 2122900058 Email:

EMSL

Attn: Howard Bader
H.A. Bader Consultants
88 Bleecker St
Suite 4E
New York, NY 10012

Fax: (212) 477-8941 Phone: 212-475-4122

Project: **DC 37 / 125 Barclay Street, NY, NY / Revised Report 9/26/01**

Customer ID: HAB50
Customer PO:
Received: 09/25/01 5:00 PM

EMSL Order: 030104914
EMSL Project ID:

Analysis Date: 9/26/2001

Asbestos Analysis of Bulk Materials by PLM via the NY State ELAP 198.1 Method

Sample	Location	Appearance	Treatment	Non-Asbestos % Fibrous	Non-Asbestos % Non-Fibrous	Asbestos % Type
D111 *030104914-0011*	1st FL Walk off Matt S	Brown Fibrous Heterogeneous	Teased Dissolved	20.00% Glass 25.00% Cellulose	55.00% Non-fibrous (other)	None Detected
D112 *030104914-0012*	1st FL Walk off Matt N	Brown Fibrous Heterogeneous	Teased Dissolved	20.00% Glass 30.00% Cellulose	50.00% Non-fibrous (other)	None Detected
D113 *030104914-0013*	2nd FL Carpet Room N	Gray Fibrous Heterogeneous	Teased Dissolved	35.00% Glass 30.00% Cellulose	35.00% Non-fibrous (other)	None Detected
D114 *030104914-0014*	2nd FL Carpet Room S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 35.00% Cellulose	55.00% Non-fibrous (other)	None Detected
D115 *030104914-0015*	5th FL Exec. Office 527 Carpet W	Tan Fibrous Heterogeneous	Teased Dissolved	30.00% Glass 25.00% Cellulose	45.00% Non-fibrous (other)	<1% Chrysotile
D116 *030104914-0016*	5th Fl Carpet Rm 501A N	Gray Fibrous Heterogeneous	Teased Dissolved	50.00% Cellulose	50.00% Non-fibrous (other)	None Detected
D117 *030104914-0017*	5th Fl Carpet Rm 540 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 40.00% Cellulose	50.00% Non-fibrous (other)	None Detected
D118 *030104914-0018*	4th Fl Carpet Rm 415 N	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 50.00% Cellulose	40.00% Non-fibrous (other)	None Detected
D119 *030104914-0019*	4th Fl Carpet Rm 407 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% Glass 45.00% Cellulose	45.00% Non-fibrous (other)	None Detected
D120 *030104914-0020*	3rd Fl CarpetRm 301 N	Gray Fibrous Heterogeneous	Teased Dissolved	15.00% Glass 45.00% Cellulose	40.00% Non-fibrous (other)	None Detected

Williams John
Analyst

Laboratory Manager
or other approved signatory

PLM has been known to miss asbestos in a small percentage of samples which contain asbestos. Negative PLM results cannot be guaranteed. Samples reported as <1% or none detected should be tested with TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. The above test must not be used by the client to claim product endorsement by NVLAP nor any agency of the United States Government.
Analysis performed by EMSL Manhattan (NVLAP #101048-9), NY ELAP 11505

PLMPointCount-1

CITY_DEP_WORBY_CANNATA_SUBP_000005641

NYC-WTC_000282006

NYC 9/11 Public Portal Document

New York Lab
307 West 38th Street, New York, NY 10018
Phone: 212-290-0051 Fax: 2122900058 Email:

EMSL

Attn: Howard Bader
H.A. Bader Consultants
88 Bleecker St
Suite 4E
New York, NY 10012
Fax: (212) 477-8941 Phone: 212-475-4122
Project: **DC 37 / 125 Barclay Street, NY, NY / Revised Report 9/26/01**

Customer ID: HAB50
Customer PO:
Received: 09/25/01 5:00 PM

EMSL Order: 030104914
EMSL Project ID:

Analysis Date: 9/26/2001

Asbestos Analysis of Bulk Materials by PLM via the NY State ELAP 198.1 Method

Sample	Location	Appearance	Treatment	Non-Asbestos %	Fibrous	Non-Asbestos %	Non-Fibrous	Asbestos % Type
D121 030104914-0021	3rd Fl CarpetRm 319 S	Gray Fibrous Heterogeneous	Teased Dissolved	10.00% 55.00%	Glass Cellulose	35.00%	Non-fibrous (other)	None Detected
D122 030104914-0022	Field Blank	White Fibrous Homogeneous	Teased Dissolved	98.00%	Cellulose	2.00%	Non-fibrous (other)	None Detected
D123 030104914-0023	Field Blank	White Fibrous Homogeneous	Teased Dissolved	98.00%	Cellulose	2.00%	Non-fibrous (other)	None Detected

Williams John
Analyst

Laboratory Manager
or other approved signatory

PLM has been known to miss asbestos in a small percentage of samples which contain asbestos. Negative PLM results cannot be guaranteed. Samples reported as <1% or none detected should be tested with TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval by EMSL Analytical, Inc. The above test must not be used by the client to claim product endorsement by NVLAP nor any agency of the United States Government.
Analysis performed by EMSL Manhattan (NVLAP #101048-9), NY ELAP 11506

PLMPointCount-1

CITY_DEP_WORBY_CANNATA_SUBP_000005642

NYC-WTC_000282007